



Customer

Sullivan Contracting Services
2299 Rudeloff Rd. East
Seguin, TX
78155, US
(830) 372-3812

Prepared By:
Shayne Henricksen
(830) 372-3812
shayne@scs-tx.com

City of Seguin
205 N. River
Seguin, TX
78155, US

Adam Rossing
(830) 386-2516
arossing@seguintexas.gov

Project: **COS - Hidalgo St. Drainage - CP**

Scope of Work

Choice Partners Contract # 25/033MR-53

ATTENTION: Adam Rossing

- Demo approx. 15-20 LF of 6" wide x 4' tall concrete wall at broken areas.
- Provide and install base material for new 65' long x 7'-9" wide channel bottom.
 - Bag exterior as needed to create 1'x1' thick edge for wall to sit on.
- Provide and install 3000 PSI concrete w/ #4 rebar at 12" OC for 65' long x 7'-9" wide x 6" thick drainage channel bottom.
- Provide and install key way for new wall tie in.
- Provide and install concrete with #4 L bars at 12" OC for 130 LF total of 1'x1' thick edge.
- Slope channel from step down to pink dot painted on job visit dated 3/19/2026. (Approx. 65 LF)
- Provide and install 130 LF total of 18-32" tall x 6" wide 3000 PSI concrete wall w/ #4 rebar at 12" OCEW from on the inside of channel only.
 - Where demoed and existing walls do not exist, concrete will be poured in the gap between the dirt and new wall face.
- Clean area of debris caused by construction.
- Washout pit for pump trucks and concrete trucks is included.
- *****City to help move existing shoring plates as needed.*****

Excluded (-)

1. After Hours, Design, Electrical, HVAC, Plumbing, Fire Sprinkler/Alarm, Permitting, Testing, any items not listed above.
2. Price excludes any owner mandated COVID-19 Testing, Procedures, and/or changes to normal work practices not covered above.
3. Due to current volatility in the market, proposal has potential to only be guaranteed for 30 days



Quote: 1826038 / Date: 4/2/2026
Project Number: 1826038

Notes

Summary

Subtotal	\$101,443.55
Taxes	\$0.00
Bonding	\$2,536.09

\$103,979.64

Accepted By

Date

.....

.....