



CONTRACT CHANGE ORDER NO. 11
RSMH STREET RECONSTRUCTION - PHASE 1
OWNER: CITY OF SEGUIN
CONTRACTOR: JORDAN FOSTER CONSTRUCTION
CONTRACT AMOUNT: \$14,502,046.39

Item No.	Item Description	Contract Quantity	Units	Unit Price	Proposal Amount	Contract Quantity + Increase (-) Decrease	Unit Price + Increase (-) Decrease	Amount + Increase (-) Decrease
P.I.32.	For furnishing and installing 8" DR 18 C-900 PVC water mains, including mandatory gravel bedding, mechanical compaction and backfill, complete in place, for the sum of,	8941	LF.	\$ 85.00	\$759,985.00	40		\$3,400.00
P.I.37.	For furnishing and installing 8" AWWA C515 Resilient Seat Gate Valves to include meg-a-lug glands, complete in place, for the sum of	61	EA.	\$ 2,500.00	\$152,500.00	1		\$2,500.00
P.I.39.	For furnishing and installing ductile iron compact main line fittings for the proposed water lines to include meg-a-lug glands, complete in place, for the sum of	10.6	TON	\$ 6,000.00	\$63,600.00	0.15		\$900.00
P.I.45.	For furnishing all material, labor and equipment for DRY connection of the proposed water main to the existing water main (regardless of size) at locations shown as shown on the Plans, complete in place, for the sum of	31	EA.	\$ 3,000.00	\$93,000.00	3		\$9,000.00
P.I.52.	For furnishing and installing OSHA required trench excavation protection on all waterlines, complete in place, for the sum of	10,101	LF.	\$1.50	\$15,151.50	60		\$90.00
P.I.54.	For furnishing all materials, labor, materials, and equipment for the inductive tracer dection wire for the water mains, complete in place, for the sum of	10,101	LF.	\$0.20	\$2,020.20	60		\$12.00
P.I.70.	For connection of proposed sewer line to existing service connections, complete in place, for the sum of	164	EA.	\$3,000.00	\$492,000.00	2		\$6,000.00
CO.58.	Install Drop (8") on Walnut Branch Sanitary Sewer MH #5	0	EA.	\$0.00	\$0.00	1	\$3,318.31	\$3,318.31
CO.59.	6" Sanitary Sewer repair on Court Street	0	EA.	\$0.00	\$0.00	1	\$26,497.44	\$26,497.44
CO.60.	For furnishing and installing 4" DR 18 C-900 PVC water main, including mandatory gravel bedding, mechanical compaction and backfill, complete in place, for the sum of	0	LF.	\$0.00	\$0.00	20	\$75.00	\$1,500.00
CO.61.	Tunnel pressure grout under Court Street	0	L.S.	\$0.00	\$0.00	1	\$9,400.00	\$9,400.00
CO.62.	For furnishing and installing 2" water connection, compacted backfill to match water main construction, at locations shown on the plans or directed by owner representative, complete in place, for the sum of	0	EA.	\$0.00	\$0.00	1	\$2,906.69	\$2,906.69
CO.63.	For furnishing and installing 2" Gate Valves, complete in place, for the sum of	0	EA.	\$0.00	\$0.00	1	\$1,800.00	\$1,800.00
CO.64.	Court Street 8" sanitary sewer and 6" water line repairs, time and material	0	LS	\$0.00	\$0.00	1	\$58,431.29	\$58,431.29
NET CONTRACT INCREASE								\$125,755.73



CONTRACT CHANGE ORDER NO. 11
RSMH STREET RECONSTRUCTION - PHASE 1
OWNER: CITY OF SEGUIN
CONTRACTOR: JORDAN FOSTER CONSTRUCTION
CONTRACT AMOUNT: \$14,502,046.39

The item numbers correspond to the following RFI's and Submittals. P.I.32., P.I.37., P.I.39. (0.13 Tons), P.I.45. (2 Each), P.I.52. (40 Linear Feet), and P.I.54. (40 Linear Feet) were for RFI #63. P.I.70. was for RFI #64. CO.58. was for RFI #59. CO.59. was for the repair of the 6" sanitary sewer line on Court Street (above the 6x6 box installation). CO.60., P.I.39. (0.02 Tons), P.I.45. (1 Each), P.I.52. (30 Linear Feet), and P.I.54. (20 Linear Feet) were for RFI #72. CO.61. was for an invoice for the tunnel pressure grouting under Court Street. The total bill was \$20,200, but TxDOT paid \$10,800. CO.62. and CO.63. were for RFI #71. CO. 64. was for time and material costs for rental for steel plates and the installation of the 8" sanitary sewer and 6" water line on Court Street. Total additional days for this change order is 26 days (RFI #63 - 3 days, 1 day for CO.58., 1 day for RFI #72, and 21 days for rain delays between March and June).

THE NET INCREASE IN THE CONTRACT AMOUNTS TO \$125,755.73 WHICH MAKES THE NEW ADJUSTED CONTRACT TOTAL \$14,502,046.39. THIS WILL BECOME A SUPPLEMENT TO THE CONTRACT AND ALL PROVISIONS WILL APPLY HERETO.

Douglas G. Faseler, City Manager
City of Seguin

Date

Joe Ramos, P.E.
City of Seguin

Date

Nathan Garza, Project Manager
City of Seguin

Date

K. Beau Perry, P.E.
TRC Engineers, Inc.

Date

Brian Hughes
Jordan Foster Construction

Date